NAMA PEMILIK PROYEK : **PT PERTAMINA EP**

NAMA PROYEK : **JASA PEMBANGUNAN FASILITAS PRODUKSI STASIUN PENGUMPUL (SP) TANJUNG MIRING BARAT & KARANGAN TIMUR**

LOKASI : **SP TANJUNG MIRING BARAT & KARANGAN TIMUR - FIELD LIMAU**

NO. KONTRAK : **SA02035383B**

REV.	TGL.	DESKRIPSI	DISIAPKAN	DIPERIKSA	DISETUJUI	DIPERIKSA	DISETUJUI
A	09/01/2026	Issued For Review	MHP	AS	MR		
			PT. PROSYMPAC OIL & GAS			PT. PERTAMINA EP	

TABEL REVISI

Rev.	Tanggal	Deskripsi

COMMENT RESPONSE SHEET

No.	Page	PERUSAHAAN's Comment	Contractor's Response	Remarks

DAFTAR ISI

TABEL REVISI **2**
COMMENT RESPONSE SHEET **3**
DAFTAR ISI **4**
1. DATA SHEET FOR FLOWMETER (ULTRASONIC) **5**

skkmigas PERTAMINA EP	**PERTAMINA EP** **REGIONAL 1 ZONA 4**	PGG

DATA SHEET FOR ULTRASONIC FLOWMETER	No. Dok. : TMBP-SP001-IN-DST-D113 Rev. : A Halaman : 5 dari 5

Tag Number	: FIT-V-006-002	Service	: FROM V-006 TO FLARE STACK
P&ID No.	: TMBP-SP001-PR-PID-D115	Equip./Line No.	: F-011-AA-6"

LINE PIPE	1	Line Size			Line Schedule	6"			Sch 40		
	2	Line ID				154 mm					
	3										
PROCESS CONDITION	4	Fluid			State	Vapor			Gas		
	5	Flow	Max	Min	Operating	0	BPD	2.83	BPD	0	BPD
	6	Pressure	Max	Design	Operating	50	psig	50	psig	3.59	psig
	7	Temperature	Max	Design	Operating	300	degF	300	degF	186.95	degF
	8	Spesific Gravity at Base			Operating	-				-	
	9	Molecular Weight				25.85					
	10	Viscosity at Operating Conditions				0.01	cP				
	11	Density @ Flow				0.07	lb/ft^3				
	12	Cp/Cv				1.19					
	13	Allowable permanen pressure lose									
	14										
LINE	15	Class	NACE	PWHT		150#		N/A		N/A	
	16	Size	Schedule	Line ID	Material	6"		Sch 40		154 mm	CS
	17	Steam out/Dry out				-					
	18										
BASIS	19	Type				Insertion Type c/w Housing					
	20	Measuring Range				0-2200 BPD					
	21										
METER	22	End Connection				Flanged Type					
	23	Size	Rating	Facing		6"		150#		RF	
	24	Flange Face Finish				RF					
	25	Flange Material				A105					
	26	Meter Body Material				316SS					(4)
	27	Tranducer Material				316SS					(4)
	28	Tranducer Type and style				Note					(4)
	29										
TRANSMITTER	30	Mounting (Integral / Remote)				Inline Pipe					
	31	Output Signal		Comm.material		4-20 mA			HART		
	32	Power Supply		Lightn.Prot. Device		230 VAC, 50 Hz			N/A		
	33	Enclosure Class		Signal Cable Conn.		IP65			½" NPTF		
	34	Area Classification		Ex Approval		Zone 2			Eex"d"		
	35	Ex Certification		Accurate		ATEX or IECEx			1% of Calibration span		
	36										
Option	37	LCD Indicator onn transmitter				YES					
	38	Remote sensor cable				YES					
	39	Special cable				Note					(5)
	40	Mounting Bracket				YES					
	41										
Purchase	42	Manufacturer									(1)
	43	Model									(2)

Notes:

1. VENDOR shall be refer to PERTAMINA HULU ROKAN Project Preferred Manufacturers List (PML).
2. VENDOR shall submit proper model number on bid proposal.
3. VENDOR shall verify and provide the calculation.
4. VTA = VENDOR to Advise.
5. Please refer to Instrument cable specification
6. Testing during FAT refer to general specification for Instrumentation Doc. No. TMBP-01-IN-SPE-105