NAMA PEMILIK PROYEK : **PT PERTAMINA EP**

NAMA PROYEK : **JASA PEMBANGUNAN FASILITAS PRODUKSI STASIUN PENGUMPUL (SP) TANJUNG MIRING BARAT & KARANGAN TIMUR**

LOKASI : **SP TANJUNG MIRING BARAT & KARANGAN TIMUR - FIELD LIMAU**

NO. KONTRAK : **SA02035383B**

REV.	TGL.	DESKRIPSI	DISIAPKAN	DIPERIKSA	DISETUJUI	DIPERIKSA	DISETUJUI
A	09/01/2026	Issued For Review	MHP	AS	MR		
			PT. PROSYMPAC OIL & GAS			PT. PERTAMINA EP	

TABEL REVISI

Rev.	Tanggal	Deskripsi

COMMENT RESPONSE SHEET

No.	Page	PERUSAHAAN's Comment	Contractor's Response	Remarks

DAFTAR ISI

TABEL REVISI **2**
COMMENT RESPONSE SHEET **3**
DAFTAR ISI **4**
1. DATA SHEET FOR LEVEL INDICATOR TABULAR **5**
1.1 LEVEL INDICATOR TABULAR LIST 6

skkmigas PERTAMINA EP	**PERTAMINA EP** **REGIONAL 1 ZONA 4**	PGG

DATA SHEET FOR LEVEL INDICATOR TABULAR	No. Dok. : TMBP-01-IN-DST-109 Rev. : A Halaman : 5 dari 6

Tag Number	: See List			Service	: See List	
P&ID No.	: See List			Equip./Line No.	: See List	
PROCESS CONDITION	1	Fluid	State	See List	See List	
	2	Operating Pressure	Design Pressure	See List psig	See List psig	
	3	Operating Temperature	Design Temperature	See List degF	See List degF	
	4	Density		See List lb/ft^3		
	5	Size Tank		See List		
GAUGE	6	Type		Tubular/Glass		
	7	Visible Length		Note		(3)
	8	Center to Center of LG		See List		(3)
	9	Connection Type		NPT Thread Type (Top-Bottom)		
	10	Chamber Material		N/A		
	11	Minimum Rating		2000 psig at 100 degF		
	12	Bolts and Nuts material		A193 B7 / A194 H2		
	13	Gasket Material		Note		(1)
	14	Glass material		Tempered Borosilicate		
	15	Shield		N/A		
	16					
	17					
GAUGE COCK	18	Type		Offset		
	19	Tank Connection		¾" ANSI 300# RF		
	20	Vent Connection		½" NPTF		
	21	Drain Connection		½" NPTF		
	22	Body Material		Carbon Steel		
	23	Trim Material		316SS		
	24	Ball Check Material		316SS		
	25	Flange Material		Carbon Steel		
	26					
OPTIONS	27	Vent Plug		½" Valve (body: A105, trim: 316SS) c/w plug		
	28	Drain		½" Valve (body: A105, trim: 316SS) c/w plug		
	29					
	30					
REMARKS	31	Name Plate (Tagging Number)		YES, 316SS		(2)
	32	Manufacture		As per AML / PML		(1)
	33	Model No.		By VENDOR		(3)
	34					

Notes:

1. VENDOR shall be refer to PT. PERTAMINA HULU ROKAN Approved Manufacturers List (AML) / Preferred Manufacturer List (PML)
2. All instrument shall be tagged with 316 SS nameplate showing tag no.
3. Vendor to Advise, subject to purchaser approval.

skkmigas PERTAMINA EP	**PERTAMINA EP** **REGIONAL 1 ZONA 4**	POG
DATA SHEET FOR LEVEL INDICATOR TABULAR		No. Dok. : TMBP-SP001-IN-DST-D109 Rev. : A Halaman : 6 dari 6

LEVEL INDICATOR TABULAR LIST

No.	Tag Number	P&ID No.	Service	Equip./Line Number	Fluid	State	Temperature (^oF)		Pressure (Psig)		Density (lb/ft^3)	Center to Center of LG (Unit)		Size Tank (Feet)
							Oper.	Design	Oper.	Design				
1	LG-V-001-001	TMBP-SP001-PR-PID-D101	PRODUCTION SEPARATOR TMB	V-001	PRODUCED LIQUID (GROSS)	LIQUID	90	200	50	230	58.86	4.38	Feet	5.48 (D) x 17.39 (T)
2	LG-V-003-001	TMBP-SP001-PR-PID-D101	PRODUCTION SEPARATOR TMB	V-003	PRODUCED LIQUID (GROSS)	LIQUID	100	150	50	100	60.55	2.3	Feet	3.3 (D) x 6.6 (T)
3	LG-V-002-001	TMBP-SP001-PR-PID-D102	TEST SEPARATOR TMB	V-002	PRODUCED LIQUID (GROSS)	LIQUID	90	200	50	230	61.23	5.94	Feet	6.99 (D) x 20 (T)
4	LG-V-004-001	TMBP-SP001-PR-PID-D102	TEST SEPARATOR TMB	V-004	PRODUCED LIQUID (GROSS)	LIQUID	100	150	50	100	59.16	2.5	Feet	3.5 (D) x 7 (T)
5	LG-V-005-001	TMBP-SP001-PR-PID-D114	PRODUCTION SCRUBBER	V-005	PRODUCED LIQUID (GROSS)	LIQUID	90	150	32	100	51.27	7.5	Feet	2.5 (D) x 8.5 (T)
6	LG-V-006-001	TMBP-SP001-PR-PID-D115	KNOCK OUT DRUM VESSEL	V-006	PRODUCED LIQUID (GROSS)	LIQUID	243	200	1.93	50	54.85	2.98	Feet	4 (D) x 11.58 (T)
7	LG-V-007-001	TMBP-SP001-PR-PID-D116	CLOSE DRAIN VESSEL	V-006	PRODUCED LIQUID (GROSS)	LIQUID	90	150	0.5	50	61.23	3.5	Feet	4.5 (D) x 15 (T)
8	LG-T-019-001	TMBP-SP001-PR-PID-D122	DIESEL STORAGE TANK	V-011	DIESEL	LIQUID	AMBIENT	100	ATM	Fuel Of Water	53.31	2500	mm	6.6 (D) x 4.9 (T)